



NEECO II AREA 1

NUEVA ECIIJA II ELECTRIC
COOPERATIVE, INC. – AREA I
Calipahan, Talavera, Nueva Ecija
Tel./Fax: (044) 411-1007; 958-0260
Email: neeco2_area1@yahoo.com.ph
Website: www.neeco2area1.com

NEECO II-AREA 1's Invitation for Bid No. NE-II-A1-2022-S05

Reference with Board Resolution No. 03-12-22, Series of 2022, the Nueva Ecija II Electric Cooperative- Area 1 (NEECO II-Area 1) invites sealed Bids from eligible contractors for:

SUPPLY OF LABOR AND MATERIALS FOR THE INSTALLATION OF EXTENSION LINE FOR THE THREE (3) PHASE POWER SUPPLY IN BF3 LOCATED AT BRGY. BUTED, TALUGTUG, NUEVA ECIIJA

Interested bidders must be previously accredited and/or for those interested bidders who may want to participate can be accredited upon completion of Accreditation requirements and full payment of non-refundable accreditation fee of Php5,000.00 which is valid for one (1) year. Accreditation requirements can be requested to this email: bac_neeco2area1@yahoo.com.ph


Accredited Bidders must use the attached form in a separate sheet of paper with company header and signature of authorized representative and submit/email it to the Bids and Awards Committee on or before March 14, 2022 5:00pm. Bids shall be addressed to the BAC Chairman:

Mr. Lorenzo Valino Jr.
BAC Chairman
Nueva Ecija II Electric Cooperative, Inc.-Area 1
Calipahan, Talavera, Nueva Ecija

For further inquiries, please contact Ms. Set Pauline M. Feliciano at (044) 411-1007 local 110 or email at bac_neeco2area1@yahoo.com.ph

NEECO II-AREA1 hereby reserves the right to reject any or all bids, to waive any formality or technicality defects therein, and accept the bid that is most advantageous to the NEECO II AREA-1, and to annul the bidding process and not award the contract at any time prior to contract award without incurring any liability to any bidder or party.

Finally, NEECO II –AREA 1 assumes no obligation to compensate any bidder or any party for any loss or expense incurred in the preparation of the bid or participation in the bidding process.


Mr. Lorenzo Valino Jr.
BAC Chairman


Engr. Nelson Dela Cruz
General Manager

PROJECT DESCRIPTION :

BILL OF MATERIALS FOR THE INSTALLATION OF POWER SUPPLY OF PILMICO ANIMAL CORPORATION AT POBLACION I, TALUGTUG, NUEVA ECIJA (TLG1086)

3 Phase = 0.502 Km.

DESCRIPTION	PROJECT REQ'MNTS.
Anchor, Expanding, 8,000 Pounds, 4 Way, Galvanized Steel	1 piece
Bolt, thimble eye 5/8x12" (angle type)	1 piece
Bolt, Carriage 3/8" X 4-1/2"	6 pieces
Bolt, Double Arming, 5/8" X 24"	6 pieces
Bolt, Oval Eye, 5/8" X 12"	2 pieces
Bolt, Oval Eye, 5/8" X 18"	2 pieces
Bolt, Machine, 1/2" X 6"	14 pieces
Bolt, Machine, 1/2" X 12"	12 pieces
Bolt, Machine, 5/8" X 12"	1 piece
Bolt, Machine, 5/8" X 14"	12 pieces
Bolt, Single Upset, 5/8" X 12"	10 pieces
Brace, Crossarm, 28", Steel	6 each
Brace, Crossarm, 60" - 18" Drop	2 pairs
Brace, Sidearm, Diagonal, 7 Feet	10 pieces
Clamp, Anchor Bonding, Single Eye Rod	1 piece
Clamp, Loop Deadend, #1/0 ACSR	6 pieces
Clamp, Deadend Strain, #1/0 ACSR	9 pieces
Clamp, Guy Straight, 3 Bolt, Heavy Duty Steel	2 pieces
Clevis, Secondary Swinging Without Spool	3 pieces
Cut Out 100A, 15KV	3 pieces
Shackle, Anchor, Forged Steel, Galvanized	2 pieces
Conductor, Bare, ACSR #1/0, AWG 6/1	2,309 meters
Connector, Compression, yho 150	10 pieces
Connector, Ground Rod (Clamp) For 5/8" Steel Rod	3 pieces
Pin, Crossarm, Steel, 5/8" X 10-3/4"	36 pieces
Insulator, Pin Type, Polyethylene	36 pieces
Insulator, Spool, 3", ANSI, Class 53 - 4	13 pieces
Insulator, Suspension, Polymer	9 pieces
Lightning Arrester, 10kv Rating (Ohio Brass Type)	3 pieces
Link, Fuse, 50 Amp	3 pieces
Nut, Eye, 5/8", Conventional	10 pieces
Rod, Anchor, Threaded, Single Eye, 5/8" X 7'	1 piece
Rod, Ground Steel, Galvanized, 5/8" X 10'	3 pieces
Washer, Square, Flat, 2-1/4" X 2-1/4" X 3/16", 13/16" Diameter Hole	71 pieces
Washer, Round, 1-3/8" Diameter With 9/16" Diameter Hole	36 pieces
Wire, Tie, Aluminum Alloy, Soft, #4 AWG	350 feet
Wire, Grounding, Aluminum Alloy, 3 Strand, #4 AWG	141 feet
Wire, Guy, Steel, 3/8", 7 Strand	50 feet

CONCRETE/STEEL MATERIAL

Pole, Concrete, 40'	12 pieces
Crossarm, Steel, 8'	15 pieces

Summary of Bid Proposal

Total Material Cost	-P
Total Labor Cost	-P
TOTAL	-P _____

Name of Bidder

BUSINESS NAME: _____
 ADDRESS: _____
 CONTACT NO.: _____
 PROPRIETOR/: _____
 DATE: _____
 TIN# NON-VAT: _____
 TIN # VAT REGISTERED: _____

PAYEE OR COMPANY NAME (*for check preparation*) _____

NO.	PARTICULARS
1	SUPPLY OF LABOR AND MATERIALS FOR THE INSTALLATION OF EXTENSION LINE FOR THE THREE (3) PHASE POWER SUPPLY IN BF3 LOCATED AT BRGY. BUTED, TALUGTUG, NUEVA ECJA
	Total Material Cost
	Total Labor Cost
	Grand Total
	Terms of Payment
	Completion Schedule (Specify if Working/Calendar Day)
	Bid Validity
	Warranty
	Other terms

Note: Bidders will attach the Bill of Materials and Work Schedule as part of their bid proposal.

 NAME AND SIGNATURE OF
 PROPRIETOR/AUTHORIZED REPRESENTATIVE